

Standard quotation for Drip, Sprinkler and Spray Irrigation system (Transport and Instalation not included)

* Area	1/4 Acers	1/2" Acers	1 acers	2 Acers
* Crop Cultivation:	Vegetable	Vegetable	Vegetable	Vegetable
* Irrigation system	Sprinkler	Sprinkler	Sprinkler	Sprinkler
* No. of Sprinkler:	36	64	130	252
* No. of Laterals :	9 nos	16	26	42
* No. of Sprinklers Per Laterals :	4 nos	4	5	6
* Spacing between laterals :	5m x 5m	5m x 5m	5m x 5m	5m x 5m
* Main line used in the system :	LDPE 50 mm	LDPE 50 mm	LDPE 50 mm	LDPE 63mm
* Lateral line used in the system :	LDPE 25 mm	LDPE 25 mm	LDPE 25 mm	LDPE 32mm
* Value	32,365.00	48,012.00	73,230.00	264,364.00

* Area	1/4 Acers	1/2" Acers
* Crop Cultivation:	Vegetable	Vegetable
* Irrigation system	Sprinkler	Sprinkler
* No. of Drippers:	220	440
* No. of Laterals :	12	24
* No. of Drippers Per Laterals :	18	18
* Main line used in the system :	LDPE 32mm	LDPE 32mm
* Lateral line used in the system :	LDPE 16mm	LDPE 16mm
* Value	23,725.00	40,000.00

* Area	1/4 Acers	1/2 Acers	1 acers	2 Acers
* Crop Cultivation:	Coconut	Coconut	Coconut	Coconut
* Irrigation system	Drip	Drip	Drip	Drip
* No. of Plants:	28	40	72	180
* No. of Laterals :	4	5	7	40
* No. of Dripper:	56	80	144	360
* Spacing between laterals :	7m x 7m	7m x 7m	7m x 7m	7m x 7m
* Main line used in the system :	LDPE 50 mm	LDPE 50 mm	LDPE 50 mm	LDPE 63mm
* Lateral line used in the system :	LDPE 16 mm	LDPE 16 mm	LDPE 16 mm	LDPE 16mm
* Value	14,719.00	19,591.00	31,604.00	54,776.00

Standard quotation for Drip, Sprinkler and Spray Irrigation system (Transport and Instalation not included)

* Area	1/4 Acers	1/2 Acers	1 acers	2 Acers
* Crop Cultivation:	Coconut	Coconut	Coconut	Coconut
* Irrigation system	Sprayers	Sprayers	Sprayers	Sprayers
* No. of Plants:	28	40	72	180
* No.of Laterals :	4	5	7	40
* No.of Sprayer :	56	80	144	360
* Spacing between laterals :	7m x 7m	7m x 7m	7m x 7m	7m x 7m
* Main line used in the system :	LDPE 50 mm	LDPE 50 mm	LDPE 50 mm	LDPE 63mm
* Lateral line used in the system :	LDPE 16 mm	LDPE 16 mm	LDPE 16 mm	LDPE 16mm
* Value	14,039.00	18,401.00	29,156.00	48,657.00

* Area	1/4 Acers	1/2 Acers	1 acers	2 Acers
* Crop Cultivation:	Banana/Papaya	Banana/Papaya	Banana/Papaya	Banana/Papaya
* Irrigation system	Drip	Drip	Drip	Drip
* No. of Plants:	110	221	440	920
* No.of Laterals :	10	13	40	46
* No.of Dripper :	220	442	880	1840
* Spacing between laterals :	7m x 7m	7m x 7m	7m x 7m	7m x 7m
* Main line used in the system :	LDPE 50 mm	LDPE 50 mm	LDPE 50 mm	LDPE 63mm
* Lateral line used in the system :	LDPE 16 mm	LDPE 16 mm	LDPE 16 mm	LDPE 16mm
* Value	25,095.00	39,001.00	70,816.00	128,492.00

* Area	1/4 Acers	1/2 Acers	1 acers	2 Acers
* Crop Cultivation:	Banana/Papaya	Banana/Papaya	Banana/Papaya	Banana/Papaya
* Irrigation system	Sprayers	Sprayers	Sprayers	Sprayers
* No. of Plants:	110	221	440	920
* No.of Laterals :	10	13	40	46
* No.of Sprayer :	220	442	880	1840
* Spacing between laterals :	3m x 3m	3m x 3m	3m x 3m	3m x 3m
* Main line used in the system :	LDPE 50 mm	LDPE 50 mm	LDPE 50 mm	LDPE 63mm
* Lateral line used in the system :	LDPE 16 mm	LDPE 16 mm	LDPE 16 mm	LDPE 16mm
* Value	21,355.00	31,487.00	55,856.00	97,212.00

Standard quotation for Drip, Sprinkler and Spray Irrigation system (Transport and Instalation not included)

* Area	1/4 Acers	1/2 Acers	1 acers
* Crop Cultivation:	Other Fruits	Other Fruits	Other Fruits
* Irrigation system	Drip	Drip	Drip
* No. of Plants:	168	320	624
* No.of Laterals :	12	32	48
* No.of Dripper :	336	640	1248
* Spacing between laterals :	2.5mx 2.5m	2.5mx 2.5m	2.5mx 2.5m
* Main line used in the system :	LDPE 50 mm	LDPE 50 mm	LDPE 50 mm
* Lateral line used in the system :	LDPE 16 mm	LDPE 16 mm	LDPE 16 mm
* Value	29,962.00	50,276.00	86,858.00

* Area	1/4 Acers	1/2 Acers	1 acers
* Crop Cultivation:	Other Fruits	Other Fruits	Other Fruits
* Irrigation system	Drip	Drip	Drip
* No. of Plants:	168	320	624
* No.of Laterals :	12	32	48
* No.of Sprayer :	336	640	1248
* Spacing between laterals :	2.5mx 2.5m	2.5mx 2.5m	2.5mx 2.5m
* Main line used in the system :	LDPE 50 mm	LDPE 50 mm	LDPE 50 mm
* Lateral line used in the system :	LDPE 16 mm	LDPE 16 mm	LDPE 16 mm
* Value	24,193.00	39,339.00	65,585.00

* Area	100Sq.f (20'x50')	2000 Sq.f (20'x100')
* Crop Cultivation:	Fruits/Flowers/Vegetable Potted plants	Fruits/Flowers/Vegetable Potted plants
* Irrigation system	Drip	Drip
* No. of Plants:	400	800
* No.of Laterals :	4	8
* No.of Sprayer :	400	800
* Spacing between laterals :	2.5mx 2.5m	2.5mx 2.5m
* Main line used in the system :	LDPE 32 mm	LDPE 50 mm
* Lateral line used in the system :	LDPE 20 mm	LDPE 16 mm
* Value	23,382.00	41,561.00

Standard quotation for Drip, Sprinkler and Spray Irrigation system (Transport and Instalation not included)

* Area	1/2 Acers	1 Acers
* Crop Cultivation:	CO -03 Grass	CO- 03 Garss
* Irrigation system	Drip	Drip
* No. of Plants:	2000	4000
* No.of Laterals :	50	100
* No.of Drippers :	2000	4000
* Spacing between laterals :	1m x 1m	1m x 1m
* Main line used in the system :	LDPE 32 mm	LDPE 50 mm
* Lateral line used in the system :	LDPE 20 mm	LDPE 16 mm
* Value	79,984.00	

* Area	96 Sq.f(12'x8f)
* Crop Cultivation:	Mushroom
* Irrigation system	Mist (Foggers)
* No.of Laterals :	2
* No.of Misters :	10
* Spacing between laterals :	2' x 2'
* Main line used in the system :	LDPE 25 mm
* Lateral line used in the system :	LDPE 25 mm
* Value	6,070.00

* Area	1 Acers (112mx36m)
* Crop Cultivation:	Ginger
* Irrigation system	Sprinklers
* No.of Laterals :	8
* No.of Sprinkler :	8
* Main line used in the system :	LDPE 63mm
* Lateral line used in the system :	LDPE 63 mm
* Value	69,540.00

* Area	1 Acers
* Crop Cultivation:	Corn
* Irrigation system	In line Dripper
* No.of Laterals :	100
* No.of Dripper line:	40
* Main line used in the system :	LDPE 50mm
* Lateral line used in the system :	30cm Spacing inline dripper
* Value	211,200.00